KOLAR DIVISION.

The 13th June 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar division, up to 10th July 1899, (inclusive) for "Restoring Kilagani tank, Registered No. 169, Mulbagal taluk." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1900.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kilagani tank, Registered No. 169, Mulbagal taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities of work required for restoring the Kilagani tank, Registered No. 169, Mulbagal taluk.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earth-work	C. yds.	12,580
Turfing	S. yds.	5,331
Old stone work	C. yds.	510
New stone work	"	1,513
Gradle stones	No.	24
Bench marks stones	"	2
Guage stone	"	1
Registered number stone	"	1
Jungle clearing (prickly-pears)	L. S.	150
Sluice No. 1—		
Earth-work	C. yds.	216
Brick in surki mortar	C. ft.	634
Stone slabs	S. ft.	164
Plastering	Sqrs.	5·00
Re-fixing old gibbets	L. S.	8
Plug with rod, complete	No.	1
Sluice No. 2—		
Earth-work	C. yds.	216
Brick in surki mortar	C. ft.	634
Stone slabs	S. ft.	164
Plastering	Sqrs.	5·00
Re-fixing old gibbets	L. S.	8
Plug with rod, complete	No.	1
Waste weir No. I—		
Earth-work	C. yds.	138
Brick in surki mortar	C. ft.	1,208
Stone slabs	S. ft.	225
Rough stone work, new	C. yds.	117
Plastering	Sqrs.	8·36
Waste weir No. II—		
Earth-work	C. yds.	224
Brick in surki mortar	C. ft.	1,750
Stone slabs	S. ft.	353
Rough stone work, new	C. yds.	186
Plastering	Sqrs.	11·56

V. ARUNACHELLA MUDALIAR,
Executive Engineer.